5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity.*
Earthwork excavation including carting of soil	C. yd.	4,546
Burnt stone in mortar with bond stones	C. ft.	30,902
Do old with new bond stones including dismantling ...	"	8,889
Flooring with slab, new	S. ft.	24,789
Do old including dismantling	"	13,387
Collecting and spreading sand	C. yd.	406
Pointing with mortar	Sqr.	301·66
Do with cement	"	374·16
Covering slabs over bridges 6" thick, new	Sq. ft.	5,100
Do removing and relaying, old	"	1,300
Coping slabs, new dressed	"	484
Do old removing and relaying	"	312
Silt clearing baling water etc.	Lump sum.	

H. L. WHEELER,
for *Assistant Engineer.*

KOLAR DIVISION.

Notice dated 29th November 1904.

The attention of the public is invited to the notification in the *Mysore Gazette* No. 49, dated 15th December 1904, inviting tenders for constructing an Inspection Lodge at Kolar Gold Fiels, Bowringpet Taluk.

Dated 7th December 1904.

The attention of the public is invited to the notification in the *Mysore Gazette* No. 49, dated 15th December 1904, calling for tenders for restoring Jannagatta tank, Registered No. 345 of Kolar Taluk.

S. A. RAMASAMI, for *Executive Engineer.*

HASSAN DIVISION.

Dated 23rd December 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 31st January 1905, for restoring Metikere tank, Registered No. 12—143, Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1906.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A.M. and 5. P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Metikere tank, Registered 12—143, Channarayapatna Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of the probable cost of restoring the Metikere tank, Registered No. 12—143, Channarayapatna Taluk.

Items of Work.	*Per.*	*Quantity.*
Bund—		
Earthwork to bund	C.yd.	12,851
Turfing the slopes	S.yd.	8,985
New stone work	C.yd.	2,716
Old stone work with new jelly	„	801
Gravel backing to revetment	„	1,606
Gauge stone	No.	1
Refixing old grade stones	„	16
Repairing and fixing new grade stones	„	5
Vis a vis stones	„	21
Register number and year stone	„	1
Sluice—		
For cutting the orifice to 9″ diameter	Lump sum	rupees.
Waste-weir—		
Excavation	C.yd.	540
Rough stone in mortar	C.ft.	2,862
Burnt stone slabs	S.ft.	17
Rough stone work, dry for apron, new	C.yd.	275
Do do old	„	191
Jelly filling	„	95
Pointing in mortar	Sqr.	3
Distribution—		
Opening out sluice channels (as detailed below): —		
Earthwork excavation	C.yd.	4,090
Rough stone work	„	161
Burnt brick in chunam	C.ft.	312
Burnt stone slabs	„	281
Plastering with surki mortar	Sqr.	11·00
Excavation	Lump sum	rupees.
Gravelling	Do	
Concrete filling	C.ft.	188

Dated 3rd January 1905.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 31st January 1905, for restoring Santesivara tank Registered No. 147, Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1906.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Santesivara tank, Registered No. 147, Channarayapatna," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of the probable cost of restoring Santesivara tank, Registered No. 147 of Channarayapatna Taluk.

Items of Work.	*Per*	*Quantity.*
Bund—		
Earthwork	C. yd.	5,535
Earthwork with lead	"	4,745
Turfing	S. yd.	9,259
New stone work	C. yd.	2,412
Old stone work with ½ new	"	115
Old stone work	"	357
Grade stone, old	No.	48
Do new	"	7
Top width stone	"	55
Gauge stone	"	1
Date and Registered No. stone	"	1
B. M. stones	"	2
Gravel backing	C. yd.	956
Repairing tunnel	Lump sum	rupees.
Sluices—		
Examining and repairing (No. 1)	Lump sum	rupees.
Blocking up (No. 1)	Do	
Earthwork	C. yd.	276
Brick in surki mortar	C. Ft.	725
Burnt stone slabs	S. Ft.	303
New stone work	C. yd.	4
Plastering with surki mortar	Lump sum	rupees.
Cutting orifices	Do	
Plug with iron rod, etc.	Do	
Waste weir—		
Earthwork	C. yd.	33
Dismantling earth and stone for left return	Lump sum	rupees.
Brick in surki mortar	C. ft.	134
Burnt stone slabs	S. ft.	14
Surki concrete	C. ft.	30
Gravelling	C. yd.	60
New stone work	C. yd.	337
Dismantling and rebuilding apron	"	63
Distribution:—		
Earthwork	C. yd.	116
New stone work	"	125
Burnt stone slabs	S. ft.	197
Supply—		
Earthwork	S. yd.	520

Dated 3rd January 1905.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 31st January 1905, for restoring Nowle tank, Registered No. 179, Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1906.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Nowle tank, Registered No. 179, Channarayapatna Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate of the probable cost of restoring Nowle tank, Registered No. 179, Channarayapatna Taluk.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yds.	9,915
Turfing	S. yds.	9,527
Gravel backing	C. yds.	1,944
New stone work	„	2,734
Old stone work	„	1,489
Grade stones	No.	44
Top width stone	„	44
Registered number and date stone	„	1
Gauge stone	„	1
B. M. stones	„	2
Clearing jungle and bushes	Lump sum Rs.	
Sluices—		
Blocking up the present sluices	No.	2
Earthwork	C. yds.	384
Brick in surki mortar	C. ft.	672
Burnt stone slabs (4½")	S. ft.	192
Do do (6")	„	134
Do do (4")	„	19
Plastering with surki mortar	Lump sum Rs.	
Cutting upper and lower orifice	Do	
Plugs with iron rods	Do	
Sluice No. 2.	Do	
Waste weir—		
Earthwork	C. yds.	228
Rough stone in surki mortar	C. ft.	1,943
Do stone work, new	C. yds.	172
Do do old	„	50
Burnt stone slabs (4")	S. ft.	628
Turfing	S. yds.	85
Plastering with surki mortar	Lump sum Rs.	
Distribution, constructing lifting dam—		
Earthwork	C. yds.	107
Rough stone work new	„	
Burnt stone slabs (6")	S. ft.	20
Do do (4")	„	117
Turfing	S. yds.	101
Supply—		
Constructing tunnel of one vent 2' × 3' with masonry wings and rough stone wings at ends, etc.	Lump sum Rs.	

Notification dated 6th January 1905.

The road from Sukravarsante in Manjarabad Taluk to Subramania being under improvement, night traffic between the 18th and 26th miles of it is considered unsafe, until further notice.

C. A. MAHADEVA SASTRI,
Executive Engineer.

BANGALORE CENTRAL JAIL.

Notification dated 17th December 1904.

Notice is hereby given that sealed tenders will be received up to 10 A. M. on Friday the 13th January 1905, by the Superintendent of the Central Jail, Bangalore, for the supply, by contract, of all kinds of wool and other articles required for the use of Jail manufactures, from 1st February 1905 to 31st January 1906, both days inclusive.

Full details of supplies required and conditions for tenders are published in the *Mysore Gazette* of 22nd December 1904.

S. RAMASWAMY IYENGAR,
Offg. Superintendent.